

2004-2005 LOCAL SAFETY SCHEME PROGRAMME				ACCIDENTS	
Location	Description	Completion Date	Cost	3 Years Before	Predicted 3 Years After
B3408 Wokingham Road junction with Downshire Way, Sperry's roundabout	Improved pedestrian facilities and reduced entry width by means of central refuge. Reduction in forward visibility.	April 05	15,000	6	3
A329 London Road from Eastern Roundabout to Running Horse Roundabout (inclusive)	Enhanced signing, anti-skid on entry and circulatory carriageway.	April 05	50,000	19	7
Opladen Way (Phase 2)	Pedestrian improvement facilities and central hatching around bend.	March 05	26,000	8	3
Yorktown Road between Rackstraws Road and Laundry Lane	General safety review / de-clutter	Sept 04	15,000	12	5
Popeswood Road and St Marks Road	Junction re-alignment, anti-skid surfacing on bends, Vehicle activated warning sign	May 05	30,000	12	4
A3095 Mill Lane junction with Crowthorne Road, Hanworth Roundabout	Re-spiralling of roundabout, improved pedestrian facilities, entry and exit widening on A3095 and traffic signal timings modifications	May 05	38,000	16	6

2005-2006 LOCAL SAFETY SCHEME PROGRAMME				ACCIDENTS	
Location	Description	Completion Date	Cost	3 Years Before	3 Years After
Hanworth Road junction with Ringmead	Improved visibility, signing, lining and possible anti-skid surfacing.	Sept 05	20,000	12	7
Broad Lane roundabout junction with Ralphs Ride	Improved visibility, signing, lining and anti-skid surfacing.	Aug 05	17,000	6	3
A321 Yorktown Road Roundabout junction with Swan Lane	Improved visibility, signing, lining and anti-skid surfacing.	Sept 05	10,000	5	3
A322 Bagshot Road roundabout junction with Nine Mile Ride	Improve lane discipline, improved signing, lining and anti-skid surfacing.	Jan 06	35,000	5	3
A322 Downshire Way roundabout junction with Arlington Business park	Improved signing, lining and anti-skid surfacing.	Nov 05	18,000	4	2
B3408 Wokingham Road roundabout junction with Western Road	Improved signing, lining and anti-skid surfacing.	Jan 06	31,000	5	2
Ringmead Area	Various road safety measures to combat specific problems	Jan 06	28,000	35	12

2006-2007 LOCAL SAFETY SCHEME PROGRAMME				ACCIDENTS	
Location	Description	Completion Date	Cost	3 Years Before	3 Years After
A330 – Borough boundary to Bracknell Road	Improved signing, lining, antiskid surfacing and other engineering measures to highlight the bends			11	7
A322 – Swinley Road / Kings Ride junction	Improved visibility by means of junction re-alignment	25,000		9	6
A330 Pigeonhouse Lane south west of Lovel Road junction	Improved signing, lining, antiskid surfacing and other engineering measures to highlight the bend.	50,000		10	8
Mill Lane Slip road between A3095 and Ellesfield Avenue	Physical measures to reduce vehicle entry speeds onto the on slip. Enhanced signing and lining.	20,000		10	7

24,000

2007-2008 LOCAL SAFETY SCHEME PROGRAMME Scheme Locations	Location Ref. (Key Accident)	Description	Est. Cost £	3 yr Casualties						3 yr Predicted Savings					
				All			Children			All			Children		
				Fatal	Serious	Slight	Fatal	Serious	Slight	Fatal	Serious	Slight	Fatal	Serious	Slight
A3095 Warfield Road Roundabout Junction with Harvest Ride	A3095	Kerb line re-alignment to increase entry deflection	£40,000	0	0	6	0	0	0	0	0	3	0	0	0
B3034 Forest Road Junction with Braziers Lane and Locks ride	B3034	Enhanced signing, lining and anti-skid road surfacing	£10,000	0	0	10	0	2	0	0	0	4	0	1	0
B3348 Dukes Ride junction with New Wokingham Road	B3348	Amendments to the traffic signals	£23,000	0	1	15	0	1	0	0	1	5	0	1	0
Ringmead (East) and Birch Hill Area	—	Specific improvements to localised areas throughout this area	£18,000	0	1	26	0	0	4	0	1	10	0	0	2
Rural Junctions throughout the Borough (Phase 1)	—	Improvements to visibility and conspicuity by means of Enhanced signing, lining and anti-skid road surfacing.	£19,000	0	0	10	0	0	0	0	0	4	0	0	0
				69			7			28			4		